

**NEPAL ELECTRICITY AUTHORITY**  
(An Undertaking of Government of Nepal)  
**DISTRIBUTION AND CONSUMER SERVICES DIRECTORATE**  
**DISTRIBUTION SYSTEM UPGRADE AND EXPANSION PROJECT**



**TENDER DOCUMENT**  
for

**Procurement of material, equipment, associated accessories and necessary installation services including design, erection, testing, and commissioning of 33/11 kV Substations and 33 kV, 11 kV, 400 V Lines and Distribution System Network - Package No. EIB-W4**

**Package No. EIB-W4 Subprojects: Bhaluwang of Dang District, Rukumkot of Rukum East District, and Sillegadha of Baitadi District**

**Single-Stage: Two-Envelope  
Tender Procedure**

**Issued on:**

**Invitation for Tenders No.: ICB-DCSD-2078/79-DSUEP-EIB-W4**


**Contract Ref. No.: ICB-DCSD-2078/79-DSUEP-EIB-W4**


**Employer: Nepal Electricity Authority**


**Country: Nepal**

**Volume IIIB of III**  
**(BoQ for 11 kV Lines, Distribution Transformers and Low-Tension lines)**

**Distribution System Upgrade and Expansion Project**  
**Distribution and Consumer Services Directorate**  
**Nepal Electricity Authority**  
**Durbarmarg, Kathmandu**  
**Tel: +977-1- 4153145**  
**Email: [dsuep@nea.org.np](mailto:dsuep@nea.org.np)**







# Table of Contents - Summary Description

## PART I TENDER PROCEDURES


<b>Section 1 - Instructions to Tenderers (ITT)</b> -----	<b>1-1</b>
This section specifies the procedures to be followed by Tenderers in the preparation and submission of their Bids. Information is also provided on the submission, opening, and evaluation of bids and on the award of contract.	
<b>Section 2 - Tender Data Sheet (TDS)</b> -----	<b>2-1</b>
This section consists of provisions that are specific to each procurement and supplement the information or requirements included in Section 1 (Instructions to Tenderers).	
<b>Section 3 - Evaluation and Qualification Criteria (EQC)</b> -----	<b>3-1</b>
This section contains the tender evaluation criteria to determine the lowest evaluated Tender and lists the necessary qualifications of Tenderers.	
<b>Section 4 - Tender Forms (TDF)</b> -----	<b>4-1</b>
This section contains the forms which are to be completed by the Tenderer and submitted as part of its Tender.	
<b>Section 5 - Eligible Countries (ELC)</b> -----	<b>5-1</b>
This section contains the list of eligible countries.	

## PART II REQUIREMENTS

<b>Section 6 - Employer's Requirements (ERQ)</b> -----	<b>6-1</b>
This section contains the Scope of Supply of Plant and Services, Specifications, the Drawings, and Supplementary Information that describe the Facilities to be procured, Personnel Requirements, Equipment Requirements, Certificates, and Change Orders.	

## PART III CONDITIONS OF CONTRACT AND CONTRACT FORMS

<b>Section 7 - General Conditions of Contract (GCC)</b> -----	<b>7-1</b>
This section contains the general clauses to be applied in all contracts. These Conditions are subject to the variations and additions set out in Section 8 (Special Conditions of Contract).	
<b>Section 8 - Special Conditions of Contract (SCC)</b> -----	<b>8-1</b>
This section contains provisions that are specific to each contract and that modify or supplement the GCC. Whenever there is a conflict, the provisions herein shall prevail over those in the GCC. The clause number of the SCC is the corresponding clause number of the GCC.	
<b>Section 9 - Contract Forms (COF)</b> -----	<b>9-1</b>
This section contains forms, which, once completed, will form part of the Contract. The forms for Performance Security and Advance Payment Security, when required, shall only be completed by the successful Tenderer after contract award.	



Volume III


Section 4: Tender Forms

Table of Contents

A	Price Schedule
---	----------------

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



## Volume III

### Section 4: Tender Forms



### Table of Contents

A	Price Schedule	
	S-1	Summary of Schedule of Plant and Mandatory Spare Parts Supplied from Abroad
	S-1-A	Schedule of Plant and Mandatory Spare Parts Supplied from Abroad for 11 kV Lines
	S-1-B	Schedule of Plant and Mandatory Spare Parts Supplied from Abroad for Distribution Transformers
	S-1-C	Schedule of Plant and Mandatory Spare Parts Supplied from Abroad for Low Tension Lines
	S-2-A	Schedule of Plant and Mandatory Spare Parts Supplied from Within the Employer's Country for 11 kV Lines
	S-2-B	Schedule of Plant and Mandatory Spare Parts Supplied from Within the Employer's Country for Distribution Transformers
	S-2-C	Schedule of Plant and Mandatory Spare Parts Supplied from Within the Employer's Country for Low Tension Lines
	S-3	Summary of Schedule of Design Services
	S-3-A	Schedule of Design Services
	S-4	Summary of Schedule of Installation and Other Services
	S-4-A	Schedule of Installation, Testing and Commissioning Works and Civil Works of 11 kV Lines
	S-4-B	Schedule of Installation, Testing and Commissioning Works and Civil Works of Distribution Transformers
	S-4-C	Schedule of Installation, Testing and Commissioning Works and Civil Works of Low Tension Lines
	S-4-D	Schedule of Environmental and Social Mitigation Works
	S-5	Summary of Schedule 1 to 4
	S-5-1	Project Component wise Summary of Schedule 1 to 4
	S-6	Schedule of Rates and Prices of Schedule No. 6: Recommended Spare Parts

Name of Tenderer \_\_\_\_\_


Signature of Tenderer \_\_\_\_\_





Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 5: Grand Summary (Excluding Custom Duty and VAT applicable in Employer's Country)


FC: USD

LC: NPR

Schedule No.	Title	Total Price	
		Foreign Currency	Local Currency
1	Plant and Mandatory Spare Parts Supplied from Abroad	-	-
2	Plant and Mandatory Spare Parts Supplied from Within the Employer's Country	-	-
3	Design Services	-	-
4	Installation and Other Services	-	-
Grand Total to be carried forward to Letter of Price Tender		-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_






Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Project Component Wise Summary of Costs (Excluding Custom Duty and VAT applicable in Employer's Country)

Item	Description	Total Price		FC: USD	LC: NPR
		Foreign Currency	Local Currency	Total Cost in Foreign Currency Only	Total Cost in Local Currency Only
1	2	3	4	5 = 3 + 4/USD Rate	6 = 3*USD Rate + 4
<b>1</b>	<b>11 kV Line</b>				
1.1	Plant and Mandatory Spare Parts Supplied from Abroad	-	-	-	-
1.2	Plant and Mandatory Spare Parts Supplied from Within the Employer's Country	-	-	-	-
1.3	Design Services	-	-	-	-
1.4	Installation and Other Services	-	-	-	-
<b>T-1</b>	<b>Sub Total of 11 kV Line</b>	-	-	-	-
<b>2</b>	<b>Distribution Transformers and Switchgear</b>				
2.1	Plant and Mandatory Spare Parts Supplied from Abroad	-	-	-	-
2.2	Plant and Mandatory Spare Parts Supplied from Within the Employer's Country	-	-	-	-
2.3	Design Services	-	-	-	-
2.4	Installation and Other Services	-	-	-	-
<b>T-2</b>	<b>Sub Total of Distribution Transformers and Switchgear</b>	-	-	-	-
<b>3</b>	<b>Low Tension Lines</b>				
3.1	Plant and Mandatory Spare Parts Supplied from Abroad	-	-	-	-
3.2	Plant and Mandatory Spare Parts Supplied from Within the Employer's Country	-	-	-	-
3.3	Design Services	-	-	-	-
3.4	Installation and Other Services	-	-	-	-
<b>T-3</b>	<b>Sub Total of Low Tension Lines</b>	-	-	-	-
<b>4</b>	<b>Environmental and Social Mitigation Works</b>				
4.1	Environmental and Social Mitigation Works	-	-	-	-
<b>T-4</b>	<b>Sub Total of Environmental and Social Mitigation Works</b>	-	-	-	-
<b>Grand Total (Sum of T-1 ... T-4)</b>		-	-	-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Summary of Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)


FC: USD

LC: NPR

Schedule No.	Title	Total Price	
		Foreign Currency	Local Currency
<b>A.</b>	<b>11 kV Line</b>	-	-
<b>B.</b>	<b>Distribution Transformers and Switchgear</b>	-	-
<b>C.</b>	<b>Low Tension Lines</b>	-	-
<b>Grand Total to be carried forward to Schedule 5</b>		-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
A.	11 kV Line							-				-	-
A.1	Conductors							-				-	-
1	XLPE Overhead Covered Conductor, 100 sq mm. with 5% Sag		kms		144.08	371.13	560.35	1,075.57				-	-
2	Mid-Span Joining Sleeve (Covered Conductor. rated min 500A)		set		274.44	706.92	1,067.34	2,048.70				-	-
3	Tension/Anchoring Assembly (including Anti-tracking Device and Socket Eye)		set		29.00	74.00	112.00	215.00				-	-
4	Polymeric Pin Ties, and Top Ties		set		29.00	74.00	112.00	215.00				-	-
5	Insulation Piercing Connectors (IPC) - Type 1		set		33.00	56.00	59.00	148.00				-	-
6	Insulation Piercing Connectors (IPC) - Type 2		set		65.00	111.00	117.00	293.00				-	-
7	Insulation Piercing Connectors (IPC) - Type 3		set		33.00	56.00	59.00	148.00				-	-
								-				-	-
A.2	Poles and Accessories							-				-	-
A.2.1	PSC Pole and Accessories							-				-	-
1	11m PSC Pole		nos.		549.00	-	-	549.00				-	-
2	Back Strap		nos.		1,483.00	-	-	1,483.00				-	-
3	Bolts with suitable nuts and washers (M16 x 100 mm)		nos.		6,808.00	-	-	6,808.00				-	-
4	Bolts with suitable nuts and washers (M16 x 235 mm)		nos.		165.00	-	-	165.00				-	-
5	Bolts with suitable nuts and washers (M16 x 50 mm)		nos.		1,236.00	-	-	1,236.00				-	-
6	Disc Type Insulatorfor 11 kV		set		1,483.00	-	-	1,483.00				-	-
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)		nos.		1,812.00	-	-	1,812.00				-	-
8	Insulator Pin for Pin Insulator of 11 kV		set		2,471.00	-	-	2,471.00				-	-
9	Pin Type Insulator for 11 kV		nos.		2,471.00	-	-	2,471.00				-	-
10	Pole Clamp with Nut, bolt and washers (PC1) with channel and support structures all complete as per design and drawings		set		906.00	-	-	906.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
11	Pole Clamp with Nut, bolt and washers (PC2) with channel and support structures all complete as per design and drawings		set		604.00	-	-	604.00				-	-
12	Pole Clamp with Nut, bolt and washers, Bottom Bracing (PC5) with channel and support structures all complete as per design and drawings		set		55.00	-	-	55.00				-	-
13	Pole Clamp with Nut, bolt and washers, Top Bracing (PC4) with channel and support structures all complete as per design and drawings		set		55.00	-	-	55.00				-	-
14	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1800 mm)		nos.		55.00	-	-	55.00				-	-
15	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1900 mm)		nos.		248.00	-	-	248.00				-	-
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2416 mm)		nos.		28.00	-	-	28.00				-	-
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2919 mm)		nos.		55.00	-	-	55.00				-	-
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 3300 mm)		nos.		248.00	-	-	248.00				-	-
19	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)		set		248.00	-	-	248.00				-	-
20	Offset Cross-Arm for Covered Conductor with all accessories complete		set		329.40	-	-	329.40				-	-
								-				-	-
A.2.2	STP Pole and Accessories - Single Circuit							-				-	-
1	11 M Steel Tubular Pole		nos.		-	1,179.00	1,779.00	2,958.00				-	-
2	Back Strap		nos.		-	1,592.00	2,402.00	3,994.00				-	-
3	Bolts with suitable nuts and washers (M16 x 100 mm)		nos.		-	6,485.00	9,785.00	16,270.00				-	-
4	Bolts with suitable nuts and washers (M16 x 235 mm)		nos.		-	118.00	178.00	296.00				-	-
5	Bolts with suitable nuts and washers (M16 x 50 mm)		nos.		-	1,415.00	2,135.00	3,550.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
6	Disc Type Insulatorfor 11 kV		set		-	1,592.00	2,402.00	3,994.00				-	-
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)		nos.		-	1,297.00	1,957.00	3,254.00				-	-
8	Insulator Pin for Pin Insulator of 11 kV		set		-	2,653.00	4,003.00	6,656.00				-	-
9	Pin Type Insulator for 11 kV		nos.		-	2,653.00	4,003.00	6,656.00				-	-
10	Pole Clamp with Nut, bolt and washers (TC1) with channel and support structures all complete as per design and drawings		set		-	1,946.00	2,936.00	4,882.00				-	-
11	Pole Clamp with Nut, bolt and washers (TC2) with channel and support structures all complete as per design and drawings		set		-	1,297.00	1,957.00	3,254.00				-	-
12	Pole Clamp with Nut, bolt and washers, Bottom Bracing (TC5) with channel and support structures all complete as per design and drawings		set		-	118.00	178.00	296.00				-	-
13	Pole Clamp with Nut, bolt and washers, Top Bracing (TC4) with channel and support structures all complete as per design and drawings		set		-	118.00	178.00	296.00				-	-
14	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1800 mm)		nos.		-	118.00	178.00	296.00				-	-
15	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1900 mm)		nos.		-	531.00	801.00	1,332.00				-	-
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2416 mm)		nos.		-	59.00	89.00	148.00				-	-
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2919 mm)		nos.		-	118.00	178.00	296.00				-	-
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 3300 mm)		nos.		-	531.00	801.00	1,332.00				-	-
19	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)		set		-	354.00	534.00	888.00				-	-
20	Offset Cross-Arm for Covered Conductor with all accessories complete		set		-	235.80	355.80	591.60				-	-
								-				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
A.2.3	STP Pole and Accessories - Double Circuit							-				-	-
1	11 m Steel Tubular Pole		nos.		407.00	1,048.00	1,582.00	3,037.00				-	-
2	Back Strap		nos.		1,099.00	2,830.00	4,272.00	8,201.00				-	-
3	Bolts with suitable nuts and washers (M16 x 100 mm)		nos.		5,047.00	12,996.00	19,617.00	37,660.00				-	-
4	Bolts with suitable nuts and washers (M16 x 235 mm)		nos.		123.00	315.00	475.00	913.00				-	-
5	Bolts with suitable nuts and washers (M16 x 50 mm)		nos.		916.00	2,358.00	3,560.00	6,834.00				-	-
6	Disc Type Insulatorfor 11 kV		set		1,099.00	2,830.00	4,272.00	8,201.00				-	-
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)		nos.		1,344.00	3,459.00	5,221.00	10,024.00				-	-
8	Insulator Pin for Pin Insulator of 11 kV		set		1,832.00	4,716.00	7,119.00	13,667.00				-	-
9	Interconnecting Clamp for MVCC		set		245.00	629.00	950.00	1,824.00				-	-
10	Pin Type Insulator for 11 kV		nos.		1,832.00	4,716.00	7,119.00	13,667.00				-	-
11	Pole Clamp with Nut, bolt and washers (TC1) with channel and support structures all complete as per design and drawings		set		1,771.00	4,559.00	6,882.00	13,212.00				-	-
12	Pole Clamp with Nut, bolt and washers (TC2) with channel and support structures all complete as per design and drawings		set		672.00	1,730.00	2,611.00	5,013.00				-	-
13	Pole Clamp with Nut, bolt and washers, Bottom Bracing (TC5) with channel and support structures all complete as per design and drawings		set		41.00	105.00	159.00	305.00				-	-
14	Pole Clamp with Nut, bolt and washers, Top Bracing (TC4) with channel and support structures all complete as per design and drawings		set		41.00	105.00	159.00	305.00				-	-
15	Preformed Pin Ties, Top Ties		set		1,832.00	4,716.00	7,119.00	13,667.00				-	-
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1600 mm)		nos.		21.00	53.00	80.00	154.00				-	-
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1640 mm)		nos.		21.00	53.00	80.00	154.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1700 mm)		nos.		855.00	2,201.00	3,323.00	6,379.00				-	-
19	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2500 mm)		nos.		489.00	1,258.00	1,899.00	3,646.00				-	-
20	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2610 mm)		nos.		41.00	105.00	159.00	305.00				-	-
21	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)		set		184.00	472.00	712.00	1,368.00				-	-
22	Tension Set with Ball and Socket Eye		set		1,099.00	2,830.00	4,272.00	8,201.00				-	-
23	Offset Cross-Arm for Covered Conductor with all accessories complete		set		488.40	419.20	632.80	1,540.40				-	-
								-				-	-
A.2.4	Stays							-				-	-
1	Pole Clamp with Nut, bolt and washers (PC3) with channel and support structures all complete as per design and drawings		set		110.00	-	-	110.00				-	-
2	Pole Clamp with Nut, bolt and washers (TC3) with channel and support structures all complete as per design and drawings		set		82.00	891.00	1,345.00	2,318.00				-	-
3	Bolts with suitable nuts and washers (M16 x 50 mm)		nos.		384.00	1,782.00	2,690.00	4,856.00				-	-
4	Bolts with suitable nuts and washers (M16 x 100 mm)		nos.		384.00	1,782.00	2,690.00	4,856.00				-	-
5	Stay Wire, (7/10 SWG minimum)		kg		1,920.00	8,910.00	13,450.00	24,280.00				-	-
6	Stay/Guy Insulator		nos.		192.00	891.00	1,345.00	2,428.00				-	-
7	Stay Turn Buckle including Thimble, (18 SWG minimum)		nos.		192.00	891.00	1,345.00	2,428.00				-	-
8	Stay I bolt, (12 inch minimum)		nos.		192.00	891.00	1,345.00	2,428.00				-	-
9	Stay I Rod/Anchor Rod, (minimum 1600 mm)		nos.		192.00	891.00	1,345.00	2,428.00				-	-
10	Bow set with Thimble		nos.		192.00	891.00	1,345.00	2,428.00				-	-
11	Stay Grip		nos.		192.00	891.00	1,345.00	2,428.00				-	-
12	Galvanized Steel Stay Plate for Installation Underground, (600 x 600 x 6 mm minimum)		nos.		192.00	891.00	1,345.00	2,428.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					6				8				
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
					A	B	C		A	B	C		
								-				-	-
A.3	Special Components							-				-	-
1	Power Arc Devices (3 Nos. per set)		set		29.00	74.00	112.00	215.00				-	-
2	13 m Steel Tubular Pole		nos.		5.00	5.00	5.00	15.00				-	-
3	14.5 m Steel Tubular Pole		nos.		5.00	5.00	5.00	15.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
B.	Distribution Transformer and Switchgear Components							-				-	-
B.1	Distribution Transformer							-				-	-
1	11/0.4kV 5 kVA 1 ph. Distribution Transformer		set		-	-	-	-				-	-
2	11/0.4kV 10 kVA 1 ph. Distribution Transformer		set		-	-	-	-				-	-
3	11/0.4kV 16 kVA 1 ph. Distribution Transformer		set		-	-	-	-				-	-
4	11/0.4kV 25kVA 3 ph. Distribution Transformer		set		-	43.00	44.00	87.00				-	-
5	11/0.4kV 50kVA 3 ph. Distribution Transformer		set		19.00	10.00	12.00	41.00				-	-
6	11/0.4kV 100kVA 3 ph. Distribution Transformer		set		13.00	2.00	2.00	17.00				-	-
7	11/0.4kV 200kVA 3 ph. Distribution Transformer		set		1.00	1.00	1.00	3.00				-	-
8	11/0.4kV 300kVA 3 ph. Distribution Transformer		set		1.00	1.00	1.00	3.00				-	-
								-				-	-
B.2	Transformer Platform							-				-	-
1	Transformer Platform for 5 kVA, Single phase Transformer including separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		-	-	-	-				-	-
2	Transformer Platform for 10 kVA, Single phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		-	-	-	-				-	-
3	Transformer Platform for 16kVA, Single phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		-	-	-	-				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
4	Transformer Platform for 25 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		-	43.00	44.00	87.00				-	-
5	Transformer Platform for 50kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		19.00	10.00	12.00	41.00				-	-
6	Transformer Platform for 100 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		13.00	2.00	2.00	17.00				-	-
7	Transformer Platform for 200 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		1.00	1.00	1.00	3.00				-	-
8	Transformer Platform for 300 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete		set		1.00	1.00	1.00	3.00				-	-
								-				-	-
B.3	Surge Protection Devices and Accessories							-				-	-
1	Surge Arrester for Single Phase Transformer Installation		set		-	-	-	-				-	-
2	9 kV Surge Arrester		set		34.00	57.00	60.00	151.00				-	-
3	Drop Out Fuse of suitable Capacity for Single Phase Transformer Installation		set		-	-	-	-				-	-
4	Drop Out Fuse of suitable Capacity		set		34.00	57.00	60.00	151.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang	Kankri Rukumkot	Dogadakedar		Bhaluwang	Kankri Rukumkot	Dogadakedar	Foreign Currency	Local Currency
					Bhaluwang		Silegadha		Bhaluwang		Silegadha		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
					A	B	C		A	B	C		
5	Outdoor Pole Mounted Distribution Panel Board (with 25A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set		set		-	-	-	-				-	-
6	Outdoor Pole Mounted Distribution Panel Board (with 50A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set		set		-	-	-	-				-	-
7	Outdoor Pole Mounted Distribution Panel Board (with 80A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set		set		-	-	-	-				-	-
8	Outdoor Pole Mounted Distribution Panel Board (with 50A TP MCCB-1 Nos, 32A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set		set		-	43.00	44.00	87.00				-	-
9	Outdoor Pole Mounted Distribution Panel Board (with 80A TP MCCB-1 Nos, 50A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set		set		19.00	10.00	12.00	41.00				-	-
10	Outdoor Pole Mounted Distribution Panel Board (with 160A TP MCCB-1 Nos, 80A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set		set		13.00	2.00	2.00	17.00				-	-
11	Outdoor Pole Mounted Distribution Panel Board (with 320A TP MCCB-1 Nos, 160A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set		set		1.00	1.00	1.00	3.00				-	-
12	Outdoor Pole Mounted Distribution Panel Board (with 500A TP MCCB-1 Nos, 250A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set		set		1.00	1.00	1.00	3.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
13	LT PVC Cable, (Al. 2 Core, 35 sq mm, Armored)		m		-	-	-	-				-	-
14	LT PVC Cable, (Al. 4 Core, 50 sq mm, Armored)		m		95.00	265.00	280.00	640.00				-	-
15	LT PVC Cable, (Al. 4 Core, 120 sq mm, Armored)		m		65.00	10.00	10.00	85.00				-	-
16	LT PVC Cable, (Al. 4 Core, 300 sq mm, Armored)		m		10.00	10.00	10.00	30.00				-	-
								-				-	-
B.4	Switchgear, Data Instrumentation System and Accessories							-				-	-
1	Load Break Switch		set		5.00	12.00	18.00	35.00				-	-
2	Transformer Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - Single Phase, with IP 67 Box, platform and connection system (Current, Voltage, Power, Power Factor, THD, Oil Temperature, Status, Daily Load Curve, local storage and transfer via GSM)		set		-	-	-	-				-	-
3	Transformer Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - 3 Phase, with IP 67 Box, platform and connection system (Current, Voltage, Power, Power Factor, THD, Oil Temperature, Status, Daily Load Curve, local storage and transfer via GSM)		set		34.00	57.00	60.00	151.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_




Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

												FC: USD		LC: NPR	
Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance		
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))		
					A	B	C		A	B	C				
4	Load Break Switch Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - 3 Phase, with IP 67 Box, platform and connection system (Current, Voltage, Daily Load Curve, Status, local storage and transfer via GSM)		set		5.00	12.00	18.00	35.00				-	-		

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
<b>C Low Tension Line</b>								-				-	-
<b>C.1 Conductor</b>								-				-	-
1	Aerial Bundled Cable with Messenger Cable 3 x 120 + 1 x 70 sq mm		kms		2.00	-	-	2.00				-	-
2	Aerial Bundled Cable with Messenger Cable 3 x 95 + 1 x 70 sq mm		kms		35.30	43.30	65.37	143.97				-	-
3	Aerial Bundled Cable with Messenger Cable 3 x 50 + 1 x 35 sq mm		kms		23.53	69.28	104.60	197.41				-	-
4	Aerial Bundled Cable with Messenger Cable 3 x 25 + 1 x 25 sq mm		kms		-	60.62	91.52	152.14				-	-
5	Aerial Bundled Cable with Messenger Cable 2 x 25 sq mm		kms		-	74.23	112.07	186.30				-	-
6	Overhead ACSR 100 sq mm. with 5% Sag with accessories all complete		kms		2.00	2.00	2.00	6.00				-	-
7	Overhead ACSR 50 sq mm. with 5% Sag with accessories all complete		kms		2.00	2.00	2.00	6.00				-	-
8	Overhead ACSR 30 sq mm. with 5% Sag with accessories all complete		kms		2.00	2.00	2.00	6.00				-	-
9	Mid-Span Cable Connector/Junction Sleeve		set		235.34	692.78	1,045.99	1,974.11				-	-
								-				-	-
<b>C.2 Poles and Accessories</b>								-				-	-
<b>C.2.1 PSC Pole and Accessories</b>								-				-	-
1	9 m PSC Pole		nos.		1,401.00	-	-	1,401.00				-	-
2	Anchor Assembly for Messenger		set		561.00	-	-	561.00				-	-
3	Suspension Assembly for Messenger		set		1,317.00	-	-	1,317.00				-	-
4	Insulated Piercing Connector		set		3,587.00	-	-	3,587.00				-	-
5	Angle Plate		set		281.00	-	-	281.00				-	-
6	Eye Nut		set		169.00	-	-	169.00				-	-
7	Insulated Cable Cap		set		2,242.00	-	-	2,242.00				-	-
8	Pig Tail with Hexagonal Nuts and Washers (16 x 203 mm)		set		1,430.00	-	-	1,430.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
				5	6				7 = Σ6	8			9 = 5 x 7
1	2	3	4	5	A	B	C	7 = Σ6	A	B	C	9 = 5 x 7	10 = Σ(π(8 x 6))
9	Pole Clamp with Nut, Bolt and Washers		set		57.00	-	-	57.00				-	-
10	Twisted Double Eye		set		281.00	-	-	281.00				-	-
								-				-	-
C.2.2	STP Pole and Accessories							-				-	-
1	8 m Steel Tubular Pole		nos.		-	4,124.00	6,227.00	10,351.00				-	-
2	Anchor Assembly for Messenger		set		-	1,650.00	2,491.00	4,141.00				-	-
3	Suspension Assembly for Messenger		set		-	3,877.00	5,854.00	9,731.00				-	-
4	Insulated Piercing Connector		set		-	10,558.00	15,942.00	26,500.00				-	-
5	Angle Plate		set		-	825.00	1,246.00	2,071.00				-	-
6	Insulated Cable Cap		set		-	6,599.00	9,964.00	16,563.00				-	-
7	Pig Tail with Fabricated Eye		set		-	4,372.00	6,601.00	10,973.00				-	-
8	Pole Clamp with Nut, Bolt and Washers		set		-	5,197.00	7,847.00	13,044.00				-	-
9	Twisted Double Eye				-	1,485.00	2,242.00	3,727.00				-	-
								-				-	-
C.2.3	Stays							-				-	-
1	Pole Clamp with Nut, bolt and washers (PC3), with channel and support structures all complete as per design and drawings		nos.		281.00	-	-	281.00				-	-
2	Pole Clamp with Nut, bolt and washers (TC3), with channel and support structures all complete as per design and drawings		nos.		-	1,650.00	2,491.00	4,141.00				-	-
3	Bolts with suitable nuts and washers (M16 x 50 mm)		nos.		562.00	3,300.00	4,982.00	8,844.00				-	-
4	Bolts with suitable nuts and washers (M16 x 100 mm)		nos.		562.00	3,300.00	4,982.00	8,844.00				-	-
5	Stay Wire, (7/10 SWG minimum)		kg		2,810.00	16,500.00	24,910.00	44,220.00				-	-
6	Stay/Guy Insulator		nos.		281.00	1,650.00	2,491.00	4,422.00				-	-
7	Stay Turn Buckle including Thimble, (18 SWG minimum)		nos.		281.00	1,650.00	2,491.00	4,422.00				-	-
8	Stay I bolt, (12 inch minimum)		set		281.00	1,650.00	2,491.00	4,422.00				-	-
9	Stay I Rod/Anchor Rod, (minimum 1600 mm)		nos.		281.00	1,650.00	2,491.00	4,422.00				-	-
10	Bow set with Thimble		nos.		281.00	1,650.00	2,491.00	4,422.00				-	-
11	Stay Grip		nos.		281.00	1,650.00	2,491.00	4,422.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
12	Galvanized Steel Stay Plate for Installation Underground, (300 x 300 x 6 mm minimum)				281.00	1,650.00	2,491.00	4,422.00				-	-
								-				-	-
C.3	Special Components							-				-	-
1	10 m PSC Pole		nos.		5.00	5.00	5.00	15.00				-	-
2	11 m PSC Pole		nos.		5.00	5.00	5.00	15.00				-	-
3	9 m Steel Tubular Pole		nos.		5.00	5.00	5.00	15.00				-	-
4	10 m Steel Tubular Pole		nos.		5.00	5.00	5.00	15.00				-	-
5	11 m Steel Tubular Pole		nos.		4.00	4.00	4.00	12.00				-	-
6	13 m Steel Tubular Pole							-				-	-
								-				-	-
C.4	Tools and Equipment							-				-	-
1	Flat wrench of different sizes for common bolts		Sets		5.00	5.00	5.00	15.00				-	-
2	Torque wrench of different sizes for common bolts		Sets		5.00	5.00	5.00	15.00				-	-
3	Pipe wrench for common bolts		Sets		5.00	5.00	5.00	15.00				-	-
4	Steel ropes (Pilot wire) 35 sq. mm		m		50.00	50.00	50.00	150.00				-	-
5	Pilot wire grips (35 sq. mm) come along clamp		Nos.		50.00	50.00	50.00	150.00				-	-
6	Rubber covered rollers,pullies(2,3 keys)		Sets		2.00	2.00	2.00	6.00				-	-
7	Portable earthing set (for Transmission line maintenance safety purpose)		Sets		5.00	5.00	5.00	15.00				-	-
8	Safety belt		Sets		20.00	20.00	20.00	60.00				-	-
9	Line operator's leather gloves		Pairs		20.00	20.00	20.00	60.00				-	-
10	Safety helmet with chinstrap and accessories		Sets		20.00	20.00	20.00	60.00				-	-
11	Insulation tester (10000 V) suitable for outdoor line testing purpose		Nos.		5.00	5.00	5.00	15.00				-	-
12	Earth resistivity tester		Nos.		5.00	5.00	5.00	15.00				-	-
13	Earthing resistance tester		Nos.		5.00	5.00	5.00	15.00				-	-
14	Double sheeve pulley block 5 MT capacity with all accessories		Sets		1.00	1.00	1.00	3.00				-	-
15	Sagging Winch 10 MT capacity hand operated		Sets		1.00	1.00	1.00	3.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 1: Plant and Mandatory Spare Parts Supplied from Abroad (Excluding Custom Duty and VAT applicable in Employer's Country)

FC: USD                      LC: NPR

Item	Description	Country of Origin	Unit	Unit Rate, CIP (Nepal Border)	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total, CIP (Nepal Border)	Total, Domestic Transportation and Insurance
				Foreign Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Foreign Currency	Local Currency
					A	B	C		A	B	C		
1	2	3	4	5	6			7 = Σ6	8			9 = 5 x 7	10 = Σ(π(8 x 6))
16	Grip suitable for ACSR DOG/RABBIT/WEASEL Conductor		Sets		5.00	5.00	5.00	15.00				-	-
17	Grip suitable for ADSS Cable		Sets		5.00	5.00	5.00	15.00				-	-
18	Grip suitable for ABC Cable		Sets		5.00	5.00	5.00	15.00				-	-
19	Safety Ladder for Distribution System Operation		Sets		5.00	5.00	5.00	15.00				-	-
20	One Set of complete tools for Maintenance/Replacement Works of Aerial Bunched Cable		Sets		5.00	5.00	5.00	15.00				-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Summary of Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

Schedule No.	Title	FC: USD	LC: NPR
		Foreign Currency	Local Currency
A.	11 kV Line	-	-
B.	Distribution Transformers and Switchgear	-	-
C.	Low Tension Lines	-	-
Grand Total to be carried forward to Schedule 5		-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price		
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency		Local Currency	Local Currency
				A	B	C		A	B	C					
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9		
			A	B	C	A		B	C						
A.	11 kV Line														
A.1	Conductors														
1	XLPE Overhead Covered Conductor, 100 sq mm. with 5% Sag	kms		144.08	371.13	560.35									
2	Mid-Span Joining Sleeve (Covered Conductor. rated min 500A)	set		274.44	706.92	1,067.34									
3	Tension/Anchoring Assembly (including Anti-tracking Device and Socket Eye)	set		29.00	74.00	112.00									
4	Polymeric Pin Ties, and Top Ties	set		29.00	74.00	112.00									
5	Insulation Piercing Connectors (IPC) - Type 1	set		33.00	56.00	59.00									
6	Insulation Piercing Connectors (IPC) - Type 2	set		65.00	111.00	117.00									
7	Insulation Piercing Connectors (IPC) - Type 3	set		33.00	56.00	59.00									
A.2	Poles and Accessories														
A.2.1	PSC Pole and Accessories														
1	11m PSC Pole	nos.		549.00	-	-									
2	Back Strap	nos.		1,483.00	-	-									
3	Bolts with suitable nuts and washers (M16 x 100 mm)	nos.		6,808.00	-	-									
4	Bolts with suitable nuts and washers (M16 x 235 mm)	nos.		165.00	-	-									
5	Bolts with suitable nuts and washers (M16 x 50 mm)	nos.		1,236.00	-	-									
6	Disc Type Insulatorfor 11 kV	set		1,483.00	-	-									
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)	nos.		1,812.00	-	-									
8	Insulator Pin for Pin Insulator of 11 kV	set		2,471.00	-	-									
9	Pin Type Insulator for 11 kV	nos.		2,471.00	-	-									
10	Pole Clamp with Nut, bolt and washers (PC1) with channel and support structures all complete as per design and drawings	set		906.00	-	-									

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency	
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
11	Pole Clamp with Nut, bolt and washers (PC2) with channel and support structures all complete as per design and drawings	set		604.00	-	-							
12	Pole Clamp with Nut, bolt and washers, Bottom Bracing (PC5) with channel and support structures all complete as per design and drawings	set		55.00	-	-							
13	Pole Clamp with Nut, bolt and washers, Top Bracing (PC4) with channel and support structures all complete as per design and drawings	set		55.00	-	-							
14	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1800 mm)	nos.		55.00	-	-							
15	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1900 mm)	nos.		248.00	-	-							
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2416 mm)	nos.		28.00	-	-							
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2919 mm)	nos.		55.00	-	-							
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 3300 mm)	nos.		248.00	-	-							
19	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)	set		248.00	-	-							
20	Offset Cross-Arm for Covered Conductor with all accessories complete	set		329.40	-	-							
A.2.2	STP Pole and Accessories - Single Circuit												
1	11 M Steel Tubular Pole	nos.		-	1,179.00	1,779.00							
2	Back Strap	nos.		-	1,592.00	2,402.00							
3	Bolts with suitable nuts and washers (M16 x 100 mm)	nos.		-	6,485.00	9,785.00							
4	Bolts with suitable nuts and washers (M16 x 235 mm)	nos.		-	118.00	178.00							
5	Bolts with suitable nuts and washers (M16 x 50 mm)	nos.		-	1,415.00	2,135.00							
6	Disc Type Insulatorfor 11 kV	set		-	1,592.00	2,402.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)	nos.		-	1,297.00	1,957.00							
8	Insulator Pin for Pin Insulator of 11 kV	set		-	2,653.00	4,003.00							
9	Pin Type Insulator for 11 kV	nos.		-	2,653.00	4,003.00							
10	Pole Clamp with Nut, bolt and washers (TC1) with channel and support structures all complete as per design and drawings	set		-	1,946.00	2,936.00							
11	Pole Clamp with Nut, bolt and washers (TC2) with channel and support structures all complete as per design and drawings	set		-	1,297.00	1,957.00							
12	Pole Clamp with Nut, bolt and washers, Bottom Bracing (TC5) with channel and support structures all complete as per design and drawings	set		-	118.00	178.00							
13	Pole Clamp with Nut, bolt and washers, Top Bracing (TC4) with channel and support structures all complete as per design and drawings	set		-	118.00	178.00							
14	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1800 mm)	nos.		-	118.00	178.00							
15	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1900 mm)	nos.		-	531.00	801.00							
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2416 mm)	nos.		-	59.00	89.00							
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2919 mm)	nos.		-	118.00	178.00							
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 3300 mm)	nos.		-	531.00	801.00							
19	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)	set		-	354.00	534.00							
20	Offset Cross-Arm for Covered Conductor with all accessories complete	set		-	235.80	355.80							
A.2.3	STP Pole and Accessories - Double Circuit												

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
			4	5				6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))
A	B	C	A	B	C								
1	11 m Steel Tubular Pole	nos.		407.00	1,048.00	1,582.00							
2	Back Strap	nos.		1,099.00	2,830.00	4,272.00							
3	Bolts with suitable nuts and washers (M16 x 100 mm)	nos.		5,047.00	12,996.00	19,617.00							
4	Bolts with suitable nuts and washers (M16 x 235 mm)	nos.		123.00	315.00	475.00							
5	Bolts with suitable nuts and washers (M16 x 50 mm)	nos.		916.00	2,358.00	3,560.00							
6	Disc Type Insulatorfor 11 kV	set		1,099.00	2,830.00	4,272.00							
7	Flat Crossarm Brace 11 kV (50 x 6 x 666 mm)	nos.		1,344.00	3,459.00	5,221.00							
8	Insulator Pin for Pin Insulator of 11 kV	set		1,832.00	4,716.00	7,119.00							
9	Interconnecting Clamp for MVCC	set		245.00	629.00	950.00							
10	Pin Type Insulator for 11 kV	nos.		1,832.00	4,716.00	7,119.00							
11	Pole Clamp with Nut, bolt and washers (TC1) with channel and support structures all complete as per design and drawings	set		1,771.00	4,559.00	6,882.00							
12	Pole Clamp with Nut, bolt and washers (TC2) with channel and support structures all complete as per design and drawings	set		672.00	1,730.00	2,611.00							
13	Pole Clamp with Nut, bolt and washers, Bottom Bracing (TC5) with channel and support structures all complete as per design and drawings	set		41.00	105.00	159.00							
14	Pole Clamp with Nut, bolt and washers, Top Bracing (TC4) with channel and support structures all complete as per design and drawings	set		41.00	105.00	159.00							
15	Preformed Pin Ties, Top Ties	set		1,832.00	4,716.00	7,119.00							
16	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1600 mm)	nos.		21.00	53.00	80.00							
17	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1640 mm)	nos.		21.00	53.00	80.00							
18	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 1700 mm)	nos.		855.00	2,201.00	3,323.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
19	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2500 mm)	nos.		489.00	1,258.00	1,899.00							
20	Steel Crossarm Channel (100 x 50 x 7.5 x 4.7 x 2610 mm)	nos.		41.00	105.00	159.00							
21	Strap for Insulator String for 11 kV (100 x 5 x 350 mm)	set		184.00	472.00	712.00							
22	Tension Set with Ball and Socket Eye	set		1,099.00	2,830.00	4,272.00							
23	Offset Cross-Arm for Covered Conductor with all accessories complete	set		488.40	419.20	632.80							
A.2.4	Stays												
1	Pole Clamp with Nut, bolt and washers (PC3) with channel and support structures all complete as per design and drawings	set		110.00	-	-							
2	Pole Clamp with Nut, bolt and washers (TC3) with channel and support structures all complete as per design and drawings	set		82.00	891.00	1,345.00							
3	Bolts with suitable nuts and washers (M16 x 50 mm)	nos.		384.00	1,782.00	2,690.00							
4	Bolts with suitable nuts and washers (M16 x 100 mm)	nos.		384.00	1,782.00	2,690.00							
5	Stay Wire, (7/10 SWG minimum)	kg		1,920.00	8,910.00	13,450.00							
6	Stay/Guy Insulator	nos.		192.00	891.00	1,345.00							
7	Stay Turn Buckle including Thimble, (18 SWG minimum)	nos.		192.00	891.00	1,345.00							
8	Stay I bolt, (12 inch minimum)	nos.		192.00	891.00	1,345.00							
9	Stay I Rod/Anchor Rod, (minimum 1600 mm)	nos.		192.00	891.00	1,345.00							
10	Bow set with Thimble	nos.		192.00	891.00	1,345.00							
11	Stay Grip	nos.		192.00	891.00	1,345.00							
12	Galvanized Steel Stay Plate for Installation Underground, (600 x 600 x 6 mm minimum)	nos.		192.00	891.00	1,345.00							
A.3	Special Components												
1	Power Arc Devices (3 Nos. per set)	set		29.00	74.00	112.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
2	13 m Steel Tubular Pole	nos.		5.00	5.00	5.00							
3	14.5 m Steel Tubular Pole	nos.		5.00	5.00	5.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha			
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
			A	B	C	A		B	C				
B.	Distribution Transformer and Switchgear Components												
B.1	Distribution Transformer												
1	11/0.4kV 5 kVA 1 ph. Distribution Transformer	set		-	-	-							
2	11/0.4kV 10 kVA 1 ph. Distribution Transformer	set		-	-	-							
3	11/0.4kV 16 kVA 1 ph. Distribution Transformer	set		-	-	-							
4	11/0.4kV 25kVA 3 ph. Distribution Transformer	set		-	43.00	44.00							
5	11/0.4kV 50kVA 3 ph. Distribution Transformer	set		19.00	10.00	12.00							
6	11/0.4kV 100kVA 3 ph. Distribution Transformer	set		13.00	2.00	2.00							
7	11/0.4kV 200kVA 3 ph. Distribution Transformer	set		1.00	1.00	1.00							
8	11/0.4kV 300kVA 3 ph. Distribution Transformer	set		1.00	1.00	1.00							
B.2	Transformer Platform												
1	Transformer Platform for 5 kVA, Single phase Transformer including separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		-	-	-							
2	Transformer Platform for 10 kVA, Single phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		-	-	-							
3	Transformer Platform for 16kVA, Single phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		-	-	-							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
			4	5				6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))
A	B	C	A	B	C								
4	Transformer Platform for 25 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		-	43.00	44.00							
5	Transformer Platform for 50kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		19.00	10.00	12.00							
6	Transformer Platform for 100 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		13.00	2.00	2.00							
7	Transformer Platform for 200 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		1.00	1.00	1.00							
8	Transformer Platform for 300 kVA, 3 phase Transformer including separate separate DO & separate LA Fitting Channels, Clamps, Nutbolts all complete	set		1.00	1.00	1.00							
B.3	Surge Protection Devices and Accessories												
1	Surge Arrester for Single Phase Transformer Installation	set		-	-	-							
2	9 kV Surge Arrester	set		34.00	57.00	60.00							
3	Drop Out Fuse of suitable Capacity for Single Phase Transformer Installation	set		-	-	-							
4	Drop Out Fuse of suitable Capacity	set		34.00	57.00	60.00							
5	Outdoor Pole Mounted Distribution Panel Board (with 25A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set	set		-	-	-							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
6	Outdoor Pole Mounted Distribution Panel Board (with 50A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set	set		-	-	-							
7	Outdoor Pole Mounted Distribution Panel Board (with 80A 2P MCCB-1 Nos with Copper Busbars and Hardware) Complete Set	set		-	-	-							
8	Outdoor Pole Mounted Distribution Panel Board (with 50A TP MCCB-1 Nos, 32A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set	set		-	43.00	44.00							
9	Outdoor Pole Mounted Distribution Panel Board (with 80A TP MCCB-1 Nos, 50A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set	set		19.00	10.00	12.00							
10	Outdoor Pole Mounted Distribution Panel Board (with 160A TP MCCB-1 Nos, 80A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set	set		13.00	2.00	2.00							
11	Outdoor Pole Mounted Distribution Panel Board (with 320A TP MCCB-1 Nos, 160A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set	set		1.00	1.00	1.00							
12	Outdoor Pole Mounted Distribution Panel Board (with 500A TP MCCB-1 Nos, 250A 4P MCCB-2Nos with Copper Busbars and Hardware) Complete Set	set		1.00	1.00	1.00							
13	LT PVC Cable, (Al. 2 Core, 35 sq mm, Armored)	m		-	-	-							
14	LT PVC Cable, (Al. 4 Core, 50 sq mm, Armored)	m		95.00	265.00	280.00							
15	LT PVC Cable, (Al. 4 Core, 120 sq mm, Armored)	m		65.00	10.00	10.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency	
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
16	LT PVC Cable, (Al. 4 Core, 300 sq mm, Armored)	m		10.00	10.00	10.00							
B.4	Switchgear, Data Instrumentation System and Accessories												
1	Load Break Switch	set		5.00	12.00	18.00							
2	Transformer Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - Single Phase, with IP 67 Box, platform and connection system (Current, Voltage, Power, Power Factor, THD, Oil Temperature, Status, Daily Load Curve, local storage and transfer via GSM)	set		-	-	-							
3	Transformer Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - 3 Phase, with IP 67 Box, platform and connection system (Current, Voltage, Power, Power Factor, THD, Oil Temperature, Status, Daily Load Curve, local storage and transfer via GSM)	set		34.00	57.00	60.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
			A	B	C	A		B	C				
4	Load Break Switch Data Instrumentation System with every minute data logging and transfer to Server at Regional Control Centre and programmed locations as per specifications all complete - 3 Phase, with IP 67 Box, platform and connection system (Current, Voltage, Daily Load Curve, Status, local storage and transfer via GSM)	set		5.00	12.00	18.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
C	Low Tension Line												
C.1	Conductor												
1	Aerial Bundled Cable with Messenger Cable 3 x 120 + 1 x 70 sq mm	kms		2.00	-	-							
2	Aerial Bundled Cable with Messenger Cable 3 x 95 + 1 x 70 sq mm	kms		35.30	43.30	65.37							
3	Aerial Bundled Cable with Messenger Cable 3 x 50 + 1 x 35 sq mm	kms		23.53	69.28	104.60							
4	Aerial Bundled Cable with Messenger Cable 3 x 25 + 1 x 25 sq mm	kms		-	60.62	91.52							
5	Aerial Bundled Cable with Messenger Cable 2 x 25 sq mm	kms		-	74.23	112.07							
6	Overhead ACSR 100 sq mm. with 5% Sag with accessories all complete	kms		2.00	2.00	2.00							
7	Overhead ACSR 50 sq mm. with 5% Sag with accessories all complete	kms		2.00	2.00	2.00							
8	Overhead ACSR 30 sq mm. with 5% Sag with accessories all complete	kms		2.00	2.00	2.00							
9	Mid-Span Cable Connector/Junction Sleeve	set		235.34	692.78	1,045.99							
C.2	Poles and Accessories												
C.2.1	PSC Pole and Accessories												
1	9 m PSC Pole	nos.		1,401.00	-	-							
2	Anchor Assembly for Messenger	set		561.00	-	-							
3	Suspension Assembly for Messenger	set		1,317.00	-	-							
4	Insulated Piercing Connector	set		3,587.00	-	-							
5	Angle Plate	set		281.00	-	-							
6	Eye Nut	set		169.00	-	-							
7	Insulated Cable Cap	set		2,242.00	-	-							
8	Pig Tail with Hexagonal Nuts and Washers (16 x 203 mm)	set		1,430.00	-	-							
9	Pole Clamp with Nut, Bolt and Washers	set		57.00	-	-							
10	Twisted Double Eye	set		281.00	-	-							
C.2.2	STP Pole and Accessories												
1	8 m Steel Tubular Pole	nos.		-	4,124.00	6,227.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
1	2	3	4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
				A	B	C		A	B	C			
	2 Anchor Assembly for Messenger	set		-	1,650.00	2,491.00							
	3 Suspension Assembly for Messenger	set		-	3,877.00	5,854.00							
	4 Insulated Piercing Connector	set		-	10,558.00	15,942.00							
	5 Angle Plate	set		-	825.00	1,246.00							
	6 Insulated Cable Cap	set		-	6,599.00	9,964.00							
	7 Pig Tail with Fabricated Eye	set		-	4,372.00	6,601.00							
	8 Pole Clamp with Nut, Bolt and Washers	set		-	5,197.00	7,847.00							
	9 Twisted Double Eye			-	1,485.00	2,242.00							
C.2.3	Stays												
1	Pole Clamp with Nut, bolt and washers (PC3), with channel and support structures all complete as per design and drawings	nos.		281.00	-	-							
2	Pole Clamp with Nut, bolt and washers (TC3), with channel and support structures all complete as per design and drawings	nos.		-	1,650.00	2,491.00							
3	Bolts with suitable nuts and washers (M16 x 50 mm)	nos.		562.00	3,300.00	4,982.00							
4	Bolts with suitable nuts and washers (M16 x 100 mm)	nos.		562.00	3,300.00	4,982.00							
5	Stay Wire, (7/10 SWG minimum)	kg		2,810.00	16,500.00	24,910.00							
6	Stay/Guy Insulator	nos.		281.00	1,650.00	2,491.00							
7	Stay Turn Buckle including Thimble, (18 SWG minimum)	nos.		281.00	1,650.00	2,491.00							
8	Stay I bolt, (12 inch minimum)	set		281.00	1,650.00	2,491.00							
9	Stay I Rod/Anchor Rod, (minimum 1600 mm)	nos.		281.00	1,650.00	2,491.00							
10	Bow set with Thimble	nos.		281.00	1,650.00	2,491.00							
11	Stay Grip	nos.		281.00	1,650.00	2,491.00							
12	Galvanized Steel Stay Plate for Installation Underground, (300 x 300 x 6 mm minimum)			281.00	1,650.00	2,491.00							
C.3	Special Components												
1	10 m PSC Pole	nos.		5.00	5.00	5.00							
2	11 m PSC Pole	nos.		5.00	5.00	5.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price		
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Local Currency		Local Currency	Local Currency
				5				7							
1	2	3	4	A	B	C	6 = Σ5	A	B	C	8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9		
3	9 m Steel Tubular Pole	nos.		5.00	5.00	5.00									
4	10 m Steel Tubular Pole	nos.		5.00	5.00	5.00									
5	11 m Steel Tubular Pole	nos.		4.00	4.00	4.00									
6	13 m Steel Tubular Pole														
C.4	Tools and Equipment														
1	Flat wrench of different sizes for common bolts	Sets		5.00	5.00	5.00									
2	Torque wrench of different sizes for common bolts	Sets		5.00	5.00	5.00									
3	Pipe wrench for common bolts	Sets		5.00	5.00	5.00									
4	Steel ropes (Pilot wire) 35 sq. mm	m		50.00	50.00	50.00									
5	Pilot wire grips (35 sq. mm) come along clamp	Nos.		50.00	50.00	50.00									
6	Rubber covered rollers,pullies(2,3 keys)	Sets		2.00	2.00	2.00									
7	Portable earthing set (for Transmission line maintenance safety purpose)	Sets		5.00	5.00	5.00									
8	Safety belt	Sets		20.00	20.00	20.00									
9	Line operator's leather gloves	Pairs		20.00	20.00	20.00									
10	Safety helmet with chinstrap and accessories	Sets		20.00	20.00	20.00									
11	Insulation tester (10000 V) suitable for outdoor line testing purpose	Nos.		5.00	5.00	5.00									
12	Earth resistivity tester	Nos.		5.00	5.00	5.00									
13	Earthing resistance tester	Nos.		5.00	5.00	5.00									
14	Double sheeve pulley block 5 MT capacity with all accessories	Sets		1.00	1.00	1.00									
15	Sagging Winch 10 MT capacity hand operated	Sets		1.00	1.00	1.00									
16	Grip suitable for ACSR DOG/RABBIT/WEASEL Conductor	Sets		5.00	5.00	5.00									
17	Grip suitable for ADSS Cable	Sets		5.00	5.00	5.00									
18	Grip suitable for ABC Cable	Sets		5.00	5.00	5.00									
19	Safety Ladder for Distribution System Operation	Sets		5.00	5.00	5.00									

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 2: Plant and Mandatory Spare Parts Supplied from Within the Employer's Country (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Unit Rate, EXWorks	Quantity			Total Quantity	Unit Rate, Domestic Transportation and Insurance, Local Currency			Total EXW Price	Total, Domestic Transportation and Insurance	Total Price
			Local Currency	Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha		Bhaluwang Bhaluwang	Kankri Rukumkot	Dogadakedar Silegadha	Local Currency	Local Currency	Local Currency
			4	5			6 = Σ5	7			8 = 4 x 6	9 = Σ(π(5 x 7))	10 = 8 + 9
1	2	3		A	B	C		A	B	C			
20	One Set of complete tools for Maintenance/Replacement Works of Aerial Bunched Cable	Sets		5.00	5.00	5.00							

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Summary of Schedule No. 3: Design Services (Excluding VAT applicable in Employer's Country)


FC: USD

LC: NPR

Schedule No.	Title	Total Price	
		Foreign	Local
A.	11 kV Line	-	-
B.	Distribution Transformers and Switchgear	-	-
C.	Low Tension Lines	-	-
Grand Total to be carried forward to Schedule 5		-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 3: Design Services (Excluding VAT applicable in Employer's Country)


FC: USD

LC: NPR

Item	Description	Unit	Quantity	Unit Price		Total Price	
				Foreign Currency Portion	Local Currency Portion	Foreign Currency Portion	Local Currency Portion
1	2	3	4	5	6	7 = 4 x 5	8 = 4 x 6
<b>A.</b>	<b>11 kV Line</b>						
1	Preconstruction Survey, Design and Drawings of 11 kV Line as per the scope of the project	kms	341.45			-	-
2	As Built Drawings, Testing and Commissioning of 11kV Line as per the scope of the project	kms	341.45			-	-
<b>B.</b>	<b>Distribution Transformers and Switchgear</b>					-	-
1	Design, Drawings, Identification of Location and Capacity of 11/0.4 kV Distribution Transformer including data communication system, Lightning Arrester, MCCB, earthing, etc. all complete as per the scope of the project	set	151.00			-	-
2	As Built Drawings, Testing and Commissioning of 11/0.4 kV Distribution Transformer including data communication system, Lightning Arrester, MCCB, earthing, etc. all complete as per the scope of the project	set	151.00			-	-
3	Design, Drawings, Identification of Location and Capacity of Switchgear like load break switches including data communication system as per the scope of the project	set	35.00			-	-
4	As Built Drawings, Testing and Commissioning of Switchgear like load break switches including data communication system as per the scope of the project	set	35.00			-	-
<b>C.</b>	<b>Low Tension Lines</b>					-	-
1	Preconstruction Survey, Design and Drawings of Low Tension Line as per the scope of the project	kms	470.03			-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 3: Design Services (Excluding VAT applicable in Employer's Country)


FC: USD

LC: NPR

Item	Description	Unit	Quantity	Unit Price		Total Price	
				Foreign Currency Portion	Local Currency Portion	Foreign Currency Portion	Local Currency Portion
1	2	3	4	5	6	7 = 4 x 5	8 = 4 x 6
2	As Built Drawings, Testing and Commissioning of Low Tension Line as per the scope of the project	kms	470.03			-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Summary of Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)

FC: USD


LC: NPR

Schedule No.	Title	Total Price	
		Foreign Currency	Local Currency
A.	11 kV Line	-	-
B.	Distribution Transformers and Switchgear	-	-
C.	Low Tension Lines	-	-
D.	Environment and Social Mitigation Works	-	-
Grand Total to be carried forward to Schedule 5		-	-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_

Single-Stage: Two-Envelope



Tender No.: ICB-DCSD-2078/79-DSUEP-EIB-W4

Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Quantity			Total Quantity	Unit Price, Local Currency			Total Price
			Bhaluwang	Kankri Rukumkot	Dogadakedar		Bhaluwang	Kankri Rukumkot	Dogadakedar	
			Bhaluwang		Silegadha		Bhaluwang		Silegadha	Local Currency
1	2	3	4			5 = Σ4	6			7 = Σ(4 x 6))
			A	B	C		A	B	C	
<b>A</b>	<b>11 kV Lines</b>									
<b>A.1</b>	<b>Conductors</b>					-				-
1	Stringing of Covered Conductor (XLPE insulated, 100 sq.mm. AAC)	kms	144.08	371.13	560.35	1,075.57				-
						-				-
<b>A.2</b>	<b>Poles and accessories</b>		-			-				-
1	Hardware and transportation of 11 m long PSC including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	Nos.	549.00	-	-	549.00				-
2	Hardware and transportation of 11 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	Nos.	407.00	2,227.00	3,361.00	5,995.00				-
3	Stay sets, with stay wire, rod, ties & insulator all complete including transportation to site.	set	192.00	891.00	1,345.00	2,428.00				-
4	Providing and laying of plain cement concrete (PCC) M15 (manual mixed) in foundation complete as per drawing and technical specifications for 11 m STP.	cum	359.28	1,965.90	2,966.95	5,292.14				-
<b>A.3</b>	<b>Dismantling Works</b>					-				-
1	Dismantling of existing HT Poles (Dismantle 11m or 10m or 9m or 8m Wooden, Steel Tubular or PSC Type poles and carry back to office store safely) all complete	Nos.	10.00	10.00	20.00	40.00				-
2	Dismantling of existing HT or LT wire (Dismantle and carry back to office store safely) all complete	kms	2.00	2.00	10.00	14.00				-
						-				-
<b>A.4</b>	<b>Reconductoring Works</b>					-				-
1	Reconductoring of 11 kV lines or LT for certain sections as double or single circuit	kms	10.00	10.00	10.00	30.00				-
2	Reconnection Works of Service Cable (Single Phase)	set	10.00	10.00	10.00	30.00				-
3	Reconnection Works of Service Cable (Three Phase)	set	10.00	10.00	10.00	30.00				-
						-				-
<b>A.5</b>	<b>Special Components</b>					-				-
1	Hardware and transportation of 13 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
2	Hardware and transportation of 14.5 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
3	Providing and laying of plain cement concrete (PCC) M15 (manual mixed) in foundation complete as per drawing and technical specifications for 13 m and 14.5 m STP.	cum	18.41	18.41	18.41	55.23				-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Quantity			Total Quantity	Unit Price, Local Currency			Total Price
			Bhaluwang	Kankri Rukumkot	Dogadakedar		Bhaluwang	Kankri Rukumkot	Dogadakedar	Local Currency
			Bhaluwang		Silegadha		Bhaluwang		Silegadha	
1	2	3	4			5 = Σ4	6			7 = Σ(4 x 6))
			A	B	C		A	B	C	
<b>B</b>	<b>Distribution Transformer</b>									
<b>B.1</b>	<b>Distribution Transformer, Distribution Panel Board, Instrumentation System, Cable all complete</b>					-				-
1	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 5 kVA, single phase	set	-	-	-	-				-
2	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 10 kVA, single phase	set	-	-	-	-				-
3	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 16 kVA, single phase	set	-	-	-	-				-
4	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 25 kVA, 3 phase	set	-	43.00	44.00	87.00				-
5	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 50 kVA, 3 phase	set	19.00	10.00	12.00	41.00				-
6	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 100 kVA, 3 phase	set	13.00	2.00	2.00	17.00				-
7	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 200 kVA, 3 phase	set	2.00	1.00	1.00	4.00				-
8	Transformer Installation and Commissioning including Platform, Distribution Panel Board & Cable all complete - 300 kVA, 3 phase	set	2.00	1.00	1.00	4.00				-
						-				-
<b>B.2</b>	<b>Switchgear and Accessories</b>					-				-
1	Surge Arrester Installation and Commissioning all complete	set	36.00	57.00	60.00	153.00				-
2	Drop-Out Fuse Installation and Commissioning all complete	set	36.00	57.00	60.00	153.00				-
3	Installation of MCCB in Single Phase Transformers (upto 150 A)	set	-	-	-	-				-
4	Installation of 3 phase MCCB ( upto 350 A)	set	34.00	56.00	59.00	149.00				-
5	Installation of 3 phase MCCB (above 350 A)	set	2.00	1.00	1.00	4.00				-
6	Supply, Installation and Commissioning of Earthing Set, all three viz. Body, Neutral and Arrester earthing, for distribution transformer all complete as per NEA Standards	set	36.00	57.00	60.00	153.00				-
7	Supply, Installation and Commissioning of Data Instrumentation System all complete - Single Phase	set	-	-	-	-				-
8	Supply, Installation and Commissioning of Data Instrumentation System all complete - 3 phase	set	36.00	57.00	60.00	153.00				-
9	Installation and Commissioning of Load Break Switches	set	5.00	12.00	18.00	35.00				-
10	Supply, Installation and Commissioning of Data Instrumentation System all complete for Load Break Switches	set	5.00	12.00	18.00	35.00				-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Quantity			Total Quantity	Unit Price, Local Currency			Total Price
			Bhaluwang	Kankri Rukumkot	Dogadakedar		Bhaluwang	Kankri Rukumkot	Dogadakedar	Local Currency
			Bhaluwang		Silegadha		Bhaluwang		Silegadha	
1	2	3	4			5 = Σ4	6			7 = Σ(4 x 6))
			A	B	C		A	B	C	
C	Low Tension Lines									
C.1	Stringing of Conductor including all accessories and hardware fittings					-				-
1	Aerial Bundled Cable with Messenger Cable 3 x 120 + 1 x 70 sq mm	kms	2.00	-	-	2.00				-
2	Aerial Bundled Cable with Messenger Cable 3 x 95 + 1 x 70 sq mm	kms	35.30	43.30	65.37	143.97				-
3	Aerial Bundled Cable with Messenger Cable 3 x 50 + 1 x 35 sq mm	kms	23.53	69.28	104.60	197.41				-
4	Aerial Bundled Cable with Messenger Cable 3 x 25 + 1 x 25 sq mm	kms	-	60.62	91.52	152.14				-
5	Aerial Bundled Cable with Messenger Cable 2 x 25 sq mm	kms	-	74.23	112.07	186.30				-
6	Overhead ACSR 100 sq mm. with 5% Sag with accessories all complete	kms	2.00	2.00	2.00	6.00				-
7	Overhead ACSR 50 sq mm. with 5% Sag with accessories all complete	kms	2.00	2.00	2.00	6.00				-
8	Overhead ACSR 30 sq mm. with 5% Sag with accessories all complete	kms	2.00	2.00	2.00	6.00				-
						-				-
C.2	Poles and accessories					-				-
1	Hardware and transportation of 9m long PSC Pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	Nos.	1,401.00	-	-	1,401.00				-
2	Hardware and transportation of 8m long Steel Tubular Pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	Nos.	-	4,124.00	6,227.00	10,351.00				-
3	Stay sets, with stay wire, rod, ties & insulator all complete including transportation to site.	set	281.00	1,650.00	2,491.00	4,422.00				-
4	Providing and laying of plain cement concrete (PCC) M15 (manual mixed) in foundation complete as per drawing and technical specifications for 9 m STP.	cum	-	2,841.60	4,290.65	7,132.25				-
C.3	Dismantling Works		-			-				-
1	Dismantling of existing LT Poles (Dismantle 9m or 8m Wooden, Steel Tubular or PSC Type poles and carry back to office store safely) all complete	set	10.00	10.00	10.00	30.00				-
2	Dismantling of existing LT Conductor-4,3 or 2 wire (Dismantle and carry back to office store safely) all complete	kms	2.00	2.00	2.00	6.00				-
						-				-
C.4	Reconductoring Works					-				-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_





Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices


Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)

LC: NPR

Item	Description	Unit	Quantity			Total Quantity	Unit Price, Local Currency			Total Price
			Bhaluwang	Kankri Rukumkot	Dogadakedar		Bhaluwang	Kankri Rukumkot	Dogadakedar	Local Currency
			Bhaluwang		Silegadha		Bhaluwang		Silegadha	
1	2	3	4			5 = Σ4	6			7 = Σ(π(4 x 6))
			A	B	C		A	B	C	
1	Reconductoring of 11 kV lines or LT for certain sections as double or single circuit	kms	10.00	10.00	10.00	30.00				-
2	Reconnection Works of Service Cable (Single Phase)	set	10.00	10.00	10.00	30.00				-
3	Reconnection Works of Service Cable (Three Phase)	set	10.00	10.00	10.00	30.00				-
						-				-
C.5	Special Components					-				-
1	Hardware and transportation of 10 m long PSC including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
2	Hardware and transportation of 11 m long PSC pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
3	Hardware and transportation of 9 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
4	Hardware and transportation of 10 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	5.00	5.00	5.00	15.00				-
5	Hardware and transportation of 11 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	4.00	4.00	4.00	12.00				-
6	Hardware and transportation of 13 m long Steel tubular pole including erection - excavation of footing, making pole vent, placing in footing, backfilling, concreting all complete	set	2.00	2.00	2.00	6.00				-
7	Providing and laying of plain cement concrete (PCC) M15 (manual mixed) in foundation complete as per drawing and technical specifications for 10, 11 and 13 m STP.	cum	9.48	9.48	9.48	28.44				-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 4: Installation and Other Services (Excluding VAT applicable in Employer's Country)


FC: USD

LC: NPR

Item	Description	Unit	Total Price	Total Price
			Foreign Currency	Local Currency
1	2	4	6	7
<b>D.</b>	<b>Environment and Social Mitigation Works</b>			
<b>D.1</b>	<b>Environment and Social Mitigation Works</b>			
1	Mitigation Works as per the ESMP Reports and as assigned by Client.	lot		-

Name of Tenderer \_\_\_\_\_

Signature of Tenderer \_\_\_\_\_



Nepal Electricity Authority  
Distribution and Consumer Services Directorate  
Distribution System Upgrade and Expansion Project  
Schedule of Rates and Prices

Schedule No. 6: Recommended Spare Parts (Excluding VAT Applicable in Employer's Country)

FC: USD

LC: NPR

Item	Description	Quantity	Unit Price		Total Price	
			CIP	EXW	Foreign Currency Portion	Local Currency Portion
			Imported Parts	Local Parts		
			Foreign Currency	Local Currency		
1	2	3	4	5	6 = 3 x 4	7 = 3 x 5
TOTAL						

Name of Tenderer \_\_\_\_\_

Signature of Tenderer\_\_\_\_\_

